



In un-anchored applications, control units are required to prevent elongation of the joint due to pressure thrust and other internal forces. Control units should be installed at the joints cataloged neutral length as shown above. Nuts should be hand tightened till snug, while the joint is at 0 psi.

CUSTOMER _____

PROJECT _____

ENGINEER _____

ARCHITECT _____

PRO OR P.O NO _____

the Metraflex company

CHICAGO

ILLINOIS

DESCRIPTION:

CONTROL UNITS

DRAWN BY :

TPH

DATE:

4-23-92

DRAWING NO:

CU