

NOTE: METRALOOPS 2" AND LARGER INSTALLED IN ANY ORIENTATION OTHER THAN HANGING DOWN MUST HAVE THE 180° RETURN SUPPORTED. (SEE INSTALLATION INSTRUCTIONS.)

CONTACT FACTORY FOR ADDITIONAL SIZES AND MOVEMENTS. ALL DIMENSIONS IN INCHES.

QTY	SIZE	MODEL	MVMT	Α	В	PSI*	WT (LBS)	SPRING FORCE**	PROJECT INFO
	2	MLG30200	+/- 1.5	18	17.375	500	15	78	
	2.5	MLG30250	+/- 1.5	21	21	387	23	83	
	3	MLG30300	+/- 1.5	24	23.375	288	39	90	
	4	MLG30400	+/- 1.5	30	28	232	54	120	
	5	MLG30500	+/- 1.5	36	32.25	191	89	186	
	6	MLG30600	+/- 1.5	42	36.75	165	135	202	
	8	MLG30800	+/- 1.5	56	44.5	212	264	260	
	10	MLG31000	+/- 1.5	68	53.25	175	430	283	
	12	MLG31200	+/- 1.5	80	61.75	160	592	390	

*Working pressure listed is the rating at 70° F. Contact factory for other pressure ratings at other temperatures and for steam applications.

**Spring force: The total force (Lbs) required to move the Metraloop its full rated movement for 150 PSI @ 70°F.

CUSTOMER:	
PROJECT:	
ENGINEER:	

REV.	1	SUPPORT BRAC	KET CHANGE DATE 2/5/2015
M for pipe	es in	ra le	2323 W. HUBBARD ST. CHICAGO, IL 60612 TEL: 312-738-3800 FAX: 312-738-0415 WWW.METRAFLEX.COM
		METR	ALOOP®
GR	00	VED ENDS,	+/- 1.5" MOVEMENT
DRAWN B	Y: D I	KISH	DATE: 10/29/2014
APPROVE	D: J(3	DATE: 10/29/2014
SCALE:		DRAWING NUM	
NC	<u> DNE</u>		MLG3-REV1