
MODEL VLVRF8 V-LOOP FOR VRF SYSTEMS ±4" MOVEMENT, COPPER ENDS



CLEANED AND BAGGED PER PRAXAIR 99

YES NO

CONTACT FACTORY FOR ADDITIONAL SIZES AND MOVEMENTS.

| QTY | PART NUMBER | NOM SIZE | TUBE OD | Α | В | MOVEMENT | PRESSURE RATING | WEIGHT |
|-----|-------------|----------|---------|---------|---------|--------------|-----------------|--------|
| | VLVRF80050 | 1/2" | 5/8" | 42-1/8" | 11-1/4" | ± 4'' | 700 PSI @ 300°F | 3 LBS |
| | VLVRF80063 | 5/8" | 3/4" | 45-3/4" | 13" | ± 4'' | 700 PSI @ 300°F | 5 LBS |
| | VLVRF80075 | 3/4" | 7/8" | 45-3/4" | 13" | ± 4'' | 700 PSI @ 300°F | 5 LBS |
| | VLVRF80100 | 1" | 1-1/8" | 47-3/8" | 13-7/8" | ± 4'' | 700 PSI @ 300°F | 7 LBS |
| | VLVRF80125 | 1-1/4" | 1-3/8" | 50" | 15-1/8" | ± 4'' | 700 PSI @ 300°F | 10 LBS |
| | VLVRF80150 | 1-1/2" | 1-5/8" | 52-5/8" | 16-1/4" | ± 4'' | 640 PSI @ 300°F | 13 LBS |
| | VLVRF80200 | 2" | 2-1/8" | 57-1/2" | 18-3/8" | <u>+</u> 4'' | 640 PSI @ 300°F | 19 LBS |

ALL VLVRF8'S ARE RATED FOR FULL VACUUM.

NOTE: COLD SPRINGING AT INSTALLATION IS RECOMMENDED. SEE INSTALLATION INSTRUCTIONS FOR DETAILS.

CUSTOMER:______
PROJECT:______
ENGINEER:

| REV. | DATE | | | | |
|--------------------|---|--|--|--|--|
| Me for pipes in | 2323 W. HUBBARD ST. CHICAGO, IL 60612 TEL: 312-738-3800 FAX: 312-738-0415 WWW.METRAFLEX.COM | | | | |
| | | | | | |

V-LOOP FOR VRF SYSTEMS, COPPER TUBE ENDS

DRAWN BY: **BDIAZ**APPROVED: **DKISH**DATE: **4/14/2022**DATE: **4/22/2022**

SCALE: DRAWING NUMBER: VLVRF8-1