



MATERIALS OF CONSTRUCTION*
 TUBE ENDS - COPPER
 HOSE & BRAID - BRONZE
 90° ELBOW - COPPER
 SPOOL - COPPER
 *OTHER MATERIALS AVAILABLE

NSF 61 - LEAD FREE
 The wetted surface of this product contacted by consumable water contains less than one quarter of one percent (0.25%) of lead by weight. Material complies with state codes and standards, where applicable, requiring reduced lead content.

NOTE: METRALOOPS 2" AND LARGER INSTALLED IN ANY ORIENTATION OTHER THAN HANGING DOWN MUST HAVE THE 180° RETURN SUPPORTED. (SEE INSTALLATION INSTRUCTIONS.)

CONTACT FACTORY FOR ADDITIONAL SIZES AND MOVEMENTS. ALL DIMENSIONS IN INCHES.

QTY	SIZE	MODEL	MVMT	A	B	PSI*	WT (LBS)	SPRING FORCE**	PROJECT INFO
	2-1/2"	MLSPR80250	±4"	25"	26-7/8"	200	18	83	
	3"	MLSPR80300	±4"	26-1/2"	31-5/8"	200	24	90	
	4"	MLSPR80400	±4"	30"	37-7/8"	140	31	120	

*Working pressure listed is the rating at 250° F.
 3" and 4" are double braided to meet pressure requirements.

**Spring force: The total force (Lbs) required to move the Metraloop its full rated movement for 150 PSI @ 70°F.

CUSTOMER: _____

PROJECT: _____

ENGINEER: _____

REV.	DATE
2323 W. HUBBARD ST. CHICAGO, IL 60612 TEL: 312-738-3800 FAX: 312-738-0415 WWW.METRAFLEX.COM	
PRESS READY METRALOOP® TUBE ENDS, +/- 4" MOVEMENT	
DRAWN BY: DKISH	DATE: 2/10/2017
APPROVED: JC	DATE: 2/10/2017
SCALE: N/A	DRAWING NUMBER: MLSPR80250-400-1